

To,
Dr. Sadanand Deshpande,
Principal,
Tilak Ayurved Mahavidyalaya,
Pune.

Sub : Repair Works at Rognidan Department.
Respected Sir,

Please go thro' the estimate given below for the repairs to be carried out at your Karve Road Campus, Pune

DEPARTMANT Roganidan Department
WORK Repair works - civil and carpentry

ESTIMATE

1	Providing and Fixing 3 Track, 3 Shutter Powdercoated aluminium windows with one s.s. net and Fixed portion above 4'0" Clear glass, Imported bearing, wool pile etc	<u>300@240 / sft</u>
2	complete. Openable window for small window. O.B.D. for walls and ceiling (for walls above 4'0"), Enamel paint for walls up to 4'0" and for doors and windows	enamel paint @ 17 /sft OBD @14/ sft
3	Enamel paint for Lab tables internally and externally 4 nos	11400 / no
4	Repairs to Lab table - Shutters 4 nos , Sides 6 nos with required ply of 6mm thk.	lumsum
5	Repairs to Door frame and Door at New Musium section 1 nos	2000/no
6	Shifting of table from cabin section to lab section 1 nos	9000/no
7	Waterproofing work for walls lumsum New drainage line 63 mm pipe for Lab tables	12000
8		130 / rft
9	including outlet pipes for sinks apox 110 rft Upvc Water line for tables including required valves and fittings. 100 rft	80/ rft
10	Partition work in g.i. frame and 8 mm thk bison panel with laminate from both the sides.	180 sft @ 250 sft
11	Electrical work Light points In casing and capping, Polycab wires, Anchor roma switches and sockets including submains for the boards, 20 nos	750 / no

12

Mislenious works such as shifting and removing
old work, removing debries etc

lum sum

Total Amount

Rs.