

**SHARIR KRIYA DEPARTMENT -CIVIL WORKS**

NO	ITEM	QTY	UNIT
1	Providing and Fixing 3 Track, 3 Shutter Powdercoated aluminium windows with one s.s. net and Fixed portion above 4'0" Clear glass, Imported bearing, wool pile etc complete. Openable window for small window.	280.00	sft
2	O.B.D. ceiling and wall with sanding two coats of putty and two coats of paint	3538.00	sft
3	Making New door Opening and Providing and fixing New door frame and shutter of overall size 3'0" x 7'0"	3.00	nos
4	Partition work in g.i. frame and 8 mm thk bison panel from both the sides.	368.00	sft
5	Mislenious works such as shifting and removing old work, removing debries etc	LUMSUM	
6	False ceiling in 8 mm ply with m.s. structure	620.00	sft
7	M.s. loft with 3 mm plate as a base, C channel frame, M.S. pipe ladder, concrete work and 2 coats of red oxide paint. 2 nos	2900.00	kg
8	Double charged vitrified flooring of size 600 x 600 in cement sand mortar.	1450.00	sft
9	Double charged vitrified skirting of size 600 x 600 in cement sand mortar.	216.00	rft
10	Painting of Tables in Enamel paint externaly	3.00	nos
11	Making new window opening on mez floor including, Providing and Fixing Lintel, plastering Punning, & removing debries	3.00	nos
12	Providing and fixing Woolen Carpet with 12 mm thk Ply as a base	300.00	sft
13	Enamel paint for walls upto 6'0"ht with sanding two coats of putty and two coats of paint	1688.00	sft
14	Shifting of table from cabin section to lab section 1 nos	1	nos
15	New drainage line 63 mm pipe for Lab tables including outlet pipes for sinks apox 110 rft	110	rft
16	Upvc Water line for tables including required valves and fittings. 100 rft	100	rft
17	Shifting of tables in the Lab area	2	Nos