ESTIMATE

To,
Principal
Tilak Ayurveda Mahavidyalaya,
Rasta Peth Pune.

Subject - Painting Work of Ground Floor Lobby and Main Entrance Area

Sr.No.	Description	Quantity	Unit	Rate	Amount
A]	Ground Floor Lobby Area				
1	Providing and appying two coat of OBD paint to lobby wall and ceiling	5210	Sqft		
2	Providing an appying two coat of oil Paint with two coat putty to lobby dado wall	564	Sqft		
3	Providing and applying two coat of apex paint to lobby column, patta and chajja	2532	Sqft		
4	Providing an appying two coat of oil Paint to railing, door and windows	2174	Sqft		
B]	Ground Floor Main Entrance Area)				
1	Providing and appying two coat of OBD paint to lobby wall and ceiling	3290	Sqft		
2	Providing an appying two coat of oil Paint with two coat putty to lobby dado wall	110	Sqft		
3	Providing and apolying two coat of apex paint to lobby column, patta and chajja	427	Sqft		
4	Providing an appying two coat of oil Paint to railing, door and windows	2321	Sqft		
			Total		
			SGST (9%)		
			CGST(9%)		
			Grand Total		

ESTIMATE

To,
Principal
Tilak Ayurveda Mahavidyalaya,
Rasta Peth Pune.

Subject - Painting Work of First Floor Lobby Area

Sr.No.	Description	Quantity	Unit	Rate	Amount
A]	First Floor Lobby Area				
1	Providing and appyling two coat of OBD paint to lobby wall, ceiling and staircase wall	7474	Sqft		
2	Providing an applying two coat of oil Paint with two coat putty to lobby dado wall and staircase dado wall	749	Sqft		
3	Providing and applying two coat of apex paint to lobby column and chajja	2291	Sqft		
4	Providing an appyling two coat of oil Paint to railing, door and windows,staircase ,gate, railing	3772	Sqft		
			Total		
			SGST (9%)		
			CGST(9%)		
			Grand Total		

ESTIMATE

To,
Principal
Tilak Ayurveda Mahavidyalaya,
Rasta Peth Pune.

Subject - Painting Work of Second Floor Lobby Area

Sr.No.	Description	Quantity	Unit	Rate	Amount
A]	Second Floor Lobby Area				
1	Providing and appyling two coat of OBD paint to lobby wall, ceiling and staircase wall	4697	Sqft		
2	Providing an aoplying two coat of oil Paint with two coat putty to lobby dado wall and staircase dado wal	775	Sqft		
3	Providing and applying two coat of apex paint to lobby column and chajja	1276	Sqft		
4	Providing an appyling two coat of oil Paint to railing, door and windows,staircase ,gate, railing	1492	Sqft		
			Total		
			SGST (9%)		
			CGST(9%)		
			Grand Total		