सोमवार । दि. ४ सप्टेंबर २०२३

PRABHAAT | Press Registration No. 1639/1957, Year 92, Issue No. :

प्रभात

www.dainikprabhat.com

प्रभात | पुणे | सोमवार, दि. ४ सप्टेंबर २०२३

गुड मॉर्निंग

बांधकाम विषयक

टिळक आयुर्वेद महाविद्यालय, रास्ता पेठ, पुणे येथील स्त्रीरोग प्रसूतीतंत्र व शरीररचना विभागाचे नूतनीकरण करावयाचे आहे. तपशीलासाठी पहा.

www.tilakayurved.org

(पा.क्र. २३०९११७०४६)

दि. २०-९-२०२३ पर्यंत दरपत्रक सादर करावी.

Principal
Tilak Ayurved Mahavidyalaya
Pune

DEPARTMENT		STREE ROG AANI PRASUTI TANTRA	
ESTIMATE			
WORK		CIVIL AND FURNITURE WORK	
NO	NO	ITEM	AMOUNT
1	A	FLOORING WORK IN 2'0" X 2'0" DIGITAL PRINT TILES FOR THE ROOM INCLUDING REMOVING OLD WORK IF REQUIRED.	
	B	SKIRTING WORK 4" HIEGHT INCLUDING REOVING OLD SKIRTING WITH DIGITAL TILES OF SIZE 2'0" X 2'0"	
	C	FINISHING SKIRTING TOP WITH POP	
	D	DADDO WORK FOR WASH HAND BASIN FOR HEIGHT 2'0"	
2	A	PROVIDING AND FIXING THREE TRACK THREE SHUTTER POWDERCOATED ALUMINIUM WINDOWS IN ALUMINIUM	
	B	REMOVING OLD WINDOW SHUTTERS	
3	A	PROVIDING AND FIXING NEW DOUBLE DOOR SHUTTER FOR MAIN DOOR WITH NEW DOOR FRAME OF WIDTH 1'6" WITH LAMINATE WITH ALL DOOR FITTINGS	
	B	PROVIDING AND FIXING CABIN DOOR WITH DOOR CLOSURE , GLASS WINDOW AND DOOR FITTINGS AND DOOR FRAME	
4		ELECTRICAL WORK WITH 1.5MM , 2.5MM, 1MM, 4 MM WIRES OF POLYCAB MAKE AS REQUIRED WITH ANCHOR ROMA SWITCHES AND PLATES IN CASING CAPING WITH ALL DROPS AND SWITCH BOARDS CONCEALED , DISTRIBUTION BOARD WITH 3 MCB ONE TWO POLE MCB , D.P. SWITCH, INCLUDING 10 TUBE LIGHTS, 4 FANS (IF REQUIRED) FAN PT 5, LIGHT PT 10, SOCKET 22	
5		PAINTING WORK	
	A	LUSTER PAINT UPTO HEIGHT 7'0" FOR WALLS AND PARTITIONS	
	B	OBD FOR WALLS , CEILING AND FOR PARTITIONS ABOVE 7'0" HEIGHT	
	C	OLD CUPBOARD PAINTING IN ENAMAL PAINT EXTERNALLY 10 NOS	
	D	OLD TABLE PAINT 5 NOS IN ENAMAL PAINT EXTERNALLY	

6		PROVIDING AND FIXING VERTICAL BLINDS FOR WINDOWS
7		PROVIDING AND FIXING WASH HAND BASIN WITH REQUIRED PLUMBING AND DRAIN ARRAGEMENTS AND GRANITE VERTICLE WITH DP AND EP
8	FURNITURE WORK	
	A	CUPBOARDS IN 18 MMM PLY FRAME AND SHELVES WITH 25 MM PLY FOR SHUTTER , LAMINATE ALL OVER WITH HANDLE , LOCK, S.S. HINGES, GLASS ETC 144 SFT
	B	SIDE TABLE , MAIN TABLE WITH DRAWERS , SHUTTERS, LAMINATE ALL OVER, HIGH QUALITY TELESCOPIC CHANNELS , HANDLES, LOCKETC COMPLETE 100 SFT
	C	PIN UP BOARD, TOWEL RODS, MIRROR, HOOKS, CHART FIXING ,AND MISLENIOUS WORKS
	D	PARTITION WORK FOR CABIN AND CUBICALS
9	REMOVING OLD WORK AND DEBRIES	
		TOTAL AMOUNT
		TAXES AS APPLICABLE EXTRA

DEPARTMENT		SHARIR RACHANA DEPARTMENT	
ESTIMATE			
WORK		CIVIL AND FURNITURE WORK	
NO	NO	ITEM	AMOUNT
1	A	FLOORING WORK IN 2'0" X 2'0" DIGITAL PRINT TILES FOR THE ROOM INCLUDING REMOVING OLD WORK IF REQUIRED.	
	B	SKIRTING WORK 4" HIEGHT INCLUDING REOVING OLD SKIRTING WITH DIGITAL TILES OF SIZE 2'0" X 2'0"	
	C	FINISHING SKIRTING TOP WITH POP	
	D	DADDO WORK FOR WALLS FOR HEIGHT 6'0" TILE SIZE 2'0" X 4'0"	
	E	CONSTRUCTION OF MASONARY INCLUDING PLASTER , DADDO FOR BODY WASH AREA AND CHEMICAL WATERPROOFING OF THE SAME	
	F	PLUMBING WORK FOR WASH BASIN, BODY WASH ETC	
	G	CONSTRUCTION OF NEW WINDOW FOR STAFF AREA INCLUDING BREAKING OF WALL	
2	A	PROVIDING AND FIXING THREE TRACK THREE SHUTTER POWDERCOATED ALUMINIUM WINDOWS IN ALUMINIUM	
	B	REMOVING OLD WINDOW SHUTTERS	
3	A	PROVIDING AND FIXING NEW DOUBLE DOOR SHUTTER FOR MAIN DOOR WITH NEW DOOR FRAME OF WIDTH 1'6" WITH LAMINATE WITH ALL DOOR FITTINGS	
	B	PROVIDING AND FIXING CABIN DOOR WITH DOOR CLOSURE , GLASS WINDOW AND DOOR FITTINGS AND DOOR FRAME	
4		ELECTRICAL WORK WITH 1.5MM , 2.5MM, 1MM, 4 MM WIRES OF POLYCAB MAKE AS REQUIRED WITH ANCHOR ROMA SWITCHES AND PLATES IN CASING CAPING WITH ALL DROPS AND SWITCH BOARDS CONCEALED , DISTRIBUTION BOARD .	
5		PAINTING WORK	
	A	LUSTER PAINT UPTO HEIGHT 7'0" FOR WALLS AND PARTITIONS	

	B	OBD FOR WALLS , CEILING AND FOR PARTITIONS ABOVE 7'0'' HEIGHT	
	C	OLD CUPBOARD PAINTING IN ENAMAL PAINT EXTERNALLY 10 NOS	
	D	OLD TABLE PAINT 5 NOS IN ENAMAL PAINT EXTERNALLY	
7		PROVIDING AND FIXING WASH HAND BASIN WITH REQUIRED PLUMBING AND DRAIN ARRAGEMENTS AND GRANITE VERTICLE WITH DP AND EP	
8	FURNITURE WORK		
	A	CUPBOARDS IN 18 MMM PLY FRAME AND SHELVES WITH 25 MM PLY FOR SHUTTER , LAMINATE ALL OVER WITH HANDLE , LOCK, S.S. HINGES, GLASS ETC 990 SFT	
	B	SIDE TABLE , MAIN TABLE WITH DRAWERS , SHUTTERS, LAMINATE ALL OVER, HIGH QUALITY TELESCOPIC CHANNELS , HANDLES, LOCKETC COMPLETE 100 SFT	
	C	PIN UP BOARD, TOWEL RODS, MIRROR, HOOKS, CHART FIXING ,AND MISLENIOUS WORKS	
	D	PARTITION WORK FOR CABIN AND CUBICALS	
9	REMOVING OLD WORK AND DEBRIES		
		TOTAL AMOUNT	
		TAXES AS APPLICABLE EXTRA	