गुरुवार । दि. ४ एप्रिल २०२४ ■ PRABHAAT | Press Registration No. 1639/1957, Year 93, Issue No. : 94

प्रभात

प्रतीक
बदल
महा

www.dainikprabhat.com

टिळक आयुर्वेद महाविद्यालय, रास्ता पेठ, पुणे येथील अगदतंत्र विभाग व स्वस्थवृत्त विभागाचे नूतनीकरण करावयाचे आहे. तपशीलासाठी पहा - www.tilakayurved.org

(मा.क्र. २४०४१३१८७२)

प्रभारी प्राचार्य
टिळक आयुर्वेद महाविद्यालय,पुणे-११

SWASTHWRITTA DEPARTMENT

NO	ITEM	AMOUNT
1	Providing and Fixing 3 Track, 3 Shutter Powdercoated aluminium windows with one s.s. net and Fixed portion above 4'0" Clear glass, Imported bearing, wool pile etc complete.Openable window for small window.	
2	O.B.D. ceiling with sanding two coats of putty and two coats of paint	
3	Making New door Opening and Providing and fixing New door frame and shutter of overall size 3'0" x 7'0"	
4	Partition work in g.i. frame and 8 mm thk bison panel from both the sides.	
5	Mislenious works such as shifting and removing old work, removing debries etc	
6	False ceiling in POP with G.I. frame	
7	M.s. loft with 3 mm plate as a base, C channel frame, M.S. pipe ladder, concrete work and 2 coats of red oxide paint.	
8	Double charged vitrified flooring of size 600 x 600 in cement sand morter.	
9	Double charged vitrified skirting of size 600 x 600 in cement sand morter.	
10	Glazed tile daddo 600 x 300 for wash hand basin in cement morter with roughfning of wall	
11	Making new window opening on mez floor including,Providing and Fixing Lintel, plastering Punning, & removing debries	
12	Providing and fixing Woolen Carpet with 12 mm thk Ply as a base	
13	Providing and applying Single coat Luster paint over Enamel base Paint for walls and partitions	
14	Providing and fixing Wash hand basin of size 16 x 22 with Piller cock, Stop cock, Inlet, UPVC water line, PVC outlet pipe etc.	
15	Electrical work 20 light points, 10 fan points, 30 - 5am plug points, 12 led fittings, 6 led tube lights, 9 cabin fans, bell point, mains and sub mains Polycab wire, anchor roma switches.	

Carpentary Work

1 Books and file storage cupboard in 18mm ply for shutters and 6 mm ply as back with Laminate all over with Glass inserted shutters, chain , lock, towerbolt, magnets etc 1'0" in depth.

2 Books and file storage cupboard in 18mm ply for shutters and 6 mm ply as back with Laminate all over , chain , lock, towerbolt, magnets etc 1'0" in depth.

3 Office table in 18 mm ply with laminate all over , 4 drawers with telescopic channels .

4 Office table in 18 mm ply with laminate all over , with sliding door and shelf. 1'3" deep .

5 Books and file storage cupboard in 18mm ply for shutters and 6 mm ply as back with Laminate all over chain , lock, towerbolt, magnets etc 1'6" in depth.

6 Door Shutter 25 mm thk with Both side laminate S.S. door fittings and Fixtures

7 Door Shutter 25 mm thk with Both side Paint S.S. door fittings and Fixtures

8 Mislenious works - Mirror, Towel rod,blind for windows

TOTAL AMOUNT

AGADTANTRA DEPARTMENT

NO	ITEM	AMOUNT
1	Providing and Fixing 3 Track, 3 Shutter Powdercoated aluminium windows with one s.s. net and Fixed portion above 4'0'' Clear glass, Imported bearing, wool pile etc complete.Openable window for small window.	
2	O.B.D. ceiling with sanding two coats of putty and two coats of paint	
3	Making New door Opening and Providing and fixing New door frame and shutter of overall size 3'0'' x 7'0''	
4	Partition work in g.i. frame and 8 mm thk bison panel from both the sides.	
5	Mislenious works such as shifting and removing old work, removing debries etc	
6	False ceiling in POP with G.I. frame	
7	M.s. loft with 3 mm plate as a base, C channel frame, M.S. pipe ladder, concrete work and 2 coats of red oxide paint.	
8	Double charged vitrified flooring of size 600 x 600 in cement sand morter.	
9	Double charged vitrified skirting of size 600 x 600 in cement sand morter.	
10	Glazed tile daddo 600 x 300 for wash hand basin in cement morter with roughfning of wall	
11	Making new window opening on mez floor including,Providing and Fixing Lintel, plastering Punning, & removing debries - 2 NOS	
12	Providing and fixing Woolen Carpet with 12 mm thk Ply as a base	
13	Providing and applying Single coat Luster paint over Enamel base Paint for walls and partitions	
14	Providing and fixing Wash hand basin of size 16 x 22 with Piller cock, Stop cock, Inlet, UPVC water line, PVC outlet pipe etc.	
15	Electrical work 20 light points, 10 fan points, 30 - 5am plug points, 12 led fittings, 6 led tube lights, 9 cabin fans, bell point, mains and sub mains Polycab wire, anchor roma switches.	

Carpentary Work

1	Books and file storage cupboard in 18mm ply for shutters and 6 mm ply as back with Laminate all over with Glass inserted shutters, chain , lock, towerbolt, magnets etc 1'0'' in depth.	

2	Books and file storage cupboard in 18mm ply for shutters and 6 mm ply as back with Laminate all over , chain , lock, towerbolt, magnets etc 1'0'' in depth.
3	Office table in 18 mm ply with laminate all over , 4 drawers with telescopic channels .
4	Furnishing old tables _ changing top and painting
5	Books and file storage cupboard in 18mm ply for shutters and 6 mm ply as back with Laminate all over chain , lock, towerbolt, magnets etc 1'6'' in depth.
6	Door Shutter 25 mm thk with Both side laminate S.S. door fittings and Fixtures
7	Door Shutter 25 mm thk with Both side Paint S.S. door fittings and Fixtures
8	Mislenious works - Mirror, Towel rod,blind for windows

TOTAL AMOUNT