Last Date of Submission - 02/07/2024.

DEPARTMENT SANSKRIT SANHITA DEPT

ESTIMATE

WORK CIVIL AND FURNITURE WORK

NO	NO	ITEM	AMOUNT
1	A	FLOORING WORK IN 2'0" X 2'0" DIGITAL PRINT TILES FOR THE ROOM INCLUDING REMOVING OLD WORK IF REQUIRED.	
	B	SKIRTING WORK 4" HIEGHT INCLUDING REOVING OLD SKIRTING WITH DIGITAL TILES OF SIZE 2'0" X 2'0"	
	C	FINISHING SKIRTING TOP WITH POP	
	D	DADDO WORK FOR WASH HAND BASIN FOR HEIGHT 2'0"	
2	A	PROVIDING AND FIXING THREE TRACK THREE SHUTTER POWDERCOATED ALUMINIUM WINDOWS IN ALUMINIUM	
	B	REMOVING OLD WINDOW SHUTTERS	
3	A	PROVIDING AND FIXING NEW DOUBLE DOOR SHUTTER FOR MAIN DOOR WITH NEW DOOR FRAME OF WIDTH 1'6" WITH LAMINATE WITH ALL DOOR FITTINGS	
	B	PROVIDING AND FIXING CABIN DOOR WITH DOOR CLOSURE , GLASS WINDOW AND DOOR FITTINGS AND DOOR FRAME AND TOILET DOOR	
4		ELECTRICAL WORK WITH 1.5MM , 2.5MM, 1MM, 4 MM WIRES OF POLYCAB MAKE AS REQUIRED WITH ANCHOR ROMA SWITCHES AND PLATES IN CASING CAPING WITH ALL DROPS AND SWITCH BOARDS CONCEALED , DISTRIBUTION BOARD WITH 3 MCB ONE TWO POLE MCB , D.P. SWITCH, INCLUDING 10 TUBE LIGHTS, 4 FANS (IF REQUIRED) FAN PT 5, LIGHT PT 10, SOCKET 22	
5		PAINTING WORK	
	A	LUSTER PAINT UPTO HEIGHT 7'0" FOR WALLS AND PARTITIONS	
	B	OBD FOR WALLS , CEILING AND FOR PARTITIONS ABOVE 7'0" HEIGHT	
	C	OLD CUPBOARD PAINTING IN ENAMAL PAINT EXTERNALLY 5 NOS	
	D	OLD TABLE PAINT 5 NOS IN ENAMAL PAINT EXTERNALLY	

6		PROVIDING AND FIXING VERTICAL BLINDS FOR WINDOWS
7		PLUMBING , DRAINAGE WORK INCLUDING COMMODE, W.H.B. ETC
8		AEROCON PARTITION
8	FURNITURE WORK	
	A	CUPBOARDS IN 18 MMM PLY FRAME AND SHELVES WITH 25 MM PLY FOR SHUTTER , LAMINATE ALL OVER WITH HANDLE , LOCK, S.S. HINGES, GLASS ETC 144 SFT
	B	SIDE TABLE , MAIN TABLE WITH DRAWERS , SHUTTERS, LAMINATE ALL OVER, HIGH QUALITY TELESCOPIC CHANNELS , HANDLES, LOCKETC COMPLETE 75 SFT
	C	PIN UP BOARD, TOWEL RODS, MIRROR, HOOKS, CHART FIXING ,AND MISLENIOUS WORKS
	D	PARTITION WORK FOR CABIN AND CUBICALS
9	REMOVING OLD WORK AND DEBRIES	

TOTAL AMOUNT

TAXES AS APPLICABLE EXTRA

DEPARTMENT WORK STATION - CLASSROOM NO 4

ESTIMATE

WORK CIVIL AND FURNITURE WORK

NO	NO	ITEM	AMOUNT
1	A	PROVIDING AND FIXING THREE TRACK THREE SHUTTER POWDERCOATED ALUMINIUM WINDOWS IN ALUMINIUM	
2		PROVIDING AND FIXING COLLAPSIBLE GATE AT MAIN DOOR	
3		WORKING PLATFORM WITH FOOT REST , KEY BOARD , MOUSE DRAWER WITH LAMINATE ALL OVER INCLUDING CABLE MANAGER ETC. 66 RFT	
4		PRINTER AND SCANNER PLATFORM IN PLYWOOD WITH STORAGE ARRANGEMENT	
5		ELECTRICAL WORK WITH 1.5MM , 2.5MM, 1MM, 4 MM WIRES OF POLYCAB MAKE AS REQUIRED WITH ANCHOR ROMA SWITCHES AND PLATES IN CASING CAPING WITH ALL DROPS AND SWITCH BOARDS CONCEALED , DISTRIBUTION BOARD WITH 3 MCB ONE TWO POLE MCB , D.P. SWITCH, INCLUDING FAN PT 2, SOCKET 80 A.C. POINT 2, POWER POINT 2	
6		CIVIL WORK INCLUDING CLOSING NALI, FIXING SKIRTING ETC	
7		MISLENIOUS WORKS	
		TOTAL AMOUNT	
		TAXES AS APPLICABLE EXTRA	

HOSTEL WORK

1 PROVIDING AND FIXING COLOUR COATED SHEETS NEAR LADIES HOSTEL BUILDING LENGTH 60 RFT X GFT HEIGHT

O.5 MM THICKNESS
50MM X 50MM X 1.6 MM PIPE FOR SHEET SUPPORT

75 MM X 40 MM CHANNEL FOR VERTICLE SUPPORT

2 MAKING TRENCH OF 4'0" WIDE AND 2'6" DEEP (AVG) , FOR LENGTH OF 350'0" APOX. AND REMOVING THE SOIL FROM THE TRENCH OUTSIDE OF THE PREMISES, LEVELLING THE SURFASES WITH ALL REQUIRED LABOUR , MATERIAL , TOOLS AND EQUIPMENTS

3 The Estimated cost for Fixing available Paving blocks in front of Ladies hostel area of apox 2000 sft.

P.C.C. base in concrete 4'' thk.
Required Levelling and Dhumas work
Block fitting
Mislenious masonary work if required.