

# प्रभात

प्रतीक  
बदलत्या  
महाराष्ट्राचे

www.dainikprabhat.com

प्रभात | पुणे | गुरुवार, दि. १३ मार्च २०२५

# गुड

# मॉर्निंग

## बांधकाम विषयक

टिळक आयुर्वेद  
महाविद्यालय, रास्ता पेठ,  
पुणे येथील द्रव्यगुण,  
रसशास्त्र, बालरोग, पंचकर्म  
विभागांचे नूतनीकरण  
करावयाचे आहे.  
तपशीलासाठी खालील  
वेबसाईट बघावी : [www.tilakayurved.org](http://www.tilakayurved.org)

(पा. क्र. २५०३१५३२२२)

प्रभारी प्राचार्य  
टिळक आयुर्वेद महाविद्यालय, पुणे-११

# ESTIMATE

## DRVYAGUN DEPARTMENT

NO	ITEM	AMOUNT
----	------	--------

### CIVIL WORK

Flooring work in Vitrified tile of size 600 x

- 1 600 in Matt finish including removing old tiles  
( as required )in cement sand mortar. 2670 sft  
Skirting work of 10" height in cement mortar
- 2 in vitrified tiles including removing old skirting  
and finishing the same in POP. 470 rft
- 3 Steel gray granite platform with s.s. sink as  
shown in drawing at two places with kadappa  
verticles 8'6"
- 4 Glazed tile dado in cement mortar and at  
window sills 120 sft
- 5 Three track three shutter windows in  
aluminium with 5mm thk glass powdercoating  
810 sft
- 6 Fixed glass winows in powder coated  
aluminium frame. 450 sft
- 7 Painting to Ceiling and Walls in Oil bound  
Distemper with two coats of putty and two  
coats of paint and primer. 4500 sft
- 8 Two coats of luster paint with two coats of  
putty, primer , aster coat including sanding of  
wall.1948 sft
- 9 Enamel painting for 8 table , 8chair 4 steel  
cupboards etc.
- 10 Electrical work 35 sockets, 40 light points, 20  
fan points, Mains, Sub main, MCB, ELCB, D.B.  
etc excluding fan, tube light, spot lights
- 11 Plumbing work for pantry and platform 3 nos  
sink

**CARPENTRY WORK**

- 1 Cupboards in 18mm plywood with laminate on both sides, as required Glass shutter with S.S. hinges, magnet , chain, Handles , Lock , back in 8 mm / 12 mm ply. 800 sft
- 2 Tables in 18 mm ply with 4 drawers or sliding shutter as designed with telescopic channels laminate all over. 125 sft
- 3 Table Refabrication - Laminate top and repairs. 120 sft
- 4 Partiton work in 18 mm ply for cubicals 144.5
- 5 Open cupboard in 18 mm ply. 75 sft
- 6 Mislenious work such as Soft board, Cable Manager, Curtain rod, hook etc.
- 7 Removing old work and debries
- 8 Granite top for Plat formcon wooden cupboard 80 sft

**TOTAL AMOUNT**

# ESTIMATE

## RASASHASTRA DEPARTMENT

NO	ITEM	AMOUNT
----	------	--------

### CIVIL WORK

- Flooring work in Vitrified tile of size 600 x
- 1 600 in Matt finish including removing old tiles  
( as required )in cement sand mortar. 1990 sft  
Skirting work of 10" height in cement mortar
  - 2 in vitrified tiles including removing old skirting  
and finishing the same in POP. 350 rft
  - 3 Wash place for washing utensils including  
flooring , waterproofing 12 sft
  - 4 Glazed tile dado in cement mortar and at  
window sills 90 sft
  - 5 Three track three shutter windows in  
aluminium with 5mm thk glass powdercoating  
225 sft
  - 6 Painting to Ceiling and Walls in Oil bound  
Distemper with two coats of putty and two  
coats of paint and primer. 5104sft
  - 7 Two coats of luster paint with two coats of  
putty, primer , aster coat including sanding of  
wall.2550 sft
  - 8 Enamel painting for 8 table , 8chair 4 steel ,  
40 Stools cupboards etc.  
Electrical work 35 sockets, 500 light points, 20
  - 9 fan points, Mains, Sub main, MCB, ELCB, D.B.  
etc excluding fan, tube light, spot lights
  - 10 Plumbing work for pantry and platform 3 nos  
sink  
M.S. loft with 2.5 mm plate as a base, c
  - 11 channel, angles as per design and .2517 sft
  - 12 M.s. staircase with M.S. tappa, railing etc.
  - 13 Thick woolen carpet over the loft and stair  
steps. 445 sft
  - 14 False ceiling for the loft and stair bottom.  
445sft

## CARPENTRY WORK

- 1 Cupboards in 18mm plywood with laminate on both sides, as required Glass shutter with S.S. hinges, magnet , chain, Handles , Lock , back in 8 mm / 12 mm ply. 630 sft
- 2 Tables in 18 mm ply with 4 drawers or sliding shutter as designed with telescopic channels laminate all over. 125 sft
- 3 Table Refabrication - Laminate top and repairs. 120 sft
- 4 Partiton work in 18 mm ply for cubicals. 210sft
- 5 Open cupboard in 18 mm ply. 75 sft
- 6 Mislenious work such as Soft board, Cable Manager, Curtain rod, hook etc.
- 7 Removing old work and debries
- 8 Shifting Lab tables and refitting the same including Plumbing carpentry work excluding Gas pipe line work . 3 nos

**TOTAL AMOUNT**

# ESTIMATE

## BALROG DEPARTMENT

INCL. SHIFTING ROG NIDAN DEPT TO NAAC ROOM

NO	ITEM	AMOUNT
----	------	--------

### CIVIL WORK

Flooring work in Vitrified tile of size 600 x

- 1 600 in Matt finish including removing old tiles

( as required )in cement sand mortar. 540 sft  
Skirting work of 10" height in cement mortar

- 2 in vitrified tiles including removing old skirting

and finishing the same in POP. 156 rft  
Painting to Ceiling and Walls in Oil bound

- 3 Distemper with two coats of putty and two coats of paint and primer. 2016 sft

Two coats of luster paint with two coats of putty, primer , aster coat including sanding of wall.2627 sft

- 5 Enamel painting for table , chair doors etc.

- 6 Touch up work for old Rog nidan deparment

Electrical work 20 sockets, 10 light points, 8

- 7 fan points, Mains, Sub main, MCB, ELCB, D.B.

etc excluding fan, tube light, spot lights

Electrical work in NAAC room as required for

- 8 museum of rog nidan

Breaking the wall for door, finishing the wall ,

- 9 providing Lintel providing and fixing plywood

door frame and 30 mm shutter with fittings

including removing debries.

Providing and Fixing wash hand Basin with

- 10 required Inlet and Out let connections

**CARPENTRY WORK**

- 1 Cupboards in 18mm plywood with laminate on both sides, as required Glass shutter with S.S. hinges, magnet , chain, Handles , Lock , back in 8 mm / 12 mm ply. 217 sft
- 2 Tables in 18 mm ply with 4 drawers or sliding shutter as designed with telescopic channels laminate all over. 122.5 sft
- 3 Table Refabrication - Laminate top and repairs. 2 nos
- 4 Partiton work in 18 mm ply for cubicals 170.5
- 5 Shifiting of cupbords , shelves to Naac room and refitting the same
- 6 Mislenious work such as Soft board, Cable Manager, Curtain rod, hook etc.
- 7 Removing old work and debries

**TOTAL AMOUNT**

# ESTIMATE

## PANCHAKRMA DEPARTMENT

NO	ITEM	AMOUNT
----	------	--------

### CIVIL WORK

Flooring work in Vitrified tile of size 600 x

- 1 600 in Matt finish including removing old tiles  
( as required )in cement sand mortar. 707 sft  
Skirting work of 10" height In cement mortar
- 2 in vitrified tiles including removing old skirting  
and finishing the same in POP. 78 rft  
Painting to Ceiling and Walls in Oil bound
- 3 Distemper with two coats of putty and two  
coats of paint and primer. 1930 sft
- 4 Electrical work including spot light and  
additional points as required for changed  
layout.
- 5 False ceiling for passage area. 70 sft
- 6 Repairs to old ceiling

### CARPENTRY WORK

- 1 Cupboards in 18mm plywood with laminate  
on both sides, as required Glass shutter with  
S.S. hinges, magnet , chain, Handles , Lock ,  
back in 8 mm / 12 mm ply. 324 sft  
Tables in 18 mm ply with 4 drawers or sliding
- 2 shutter as designed with telescopic channels  
laminate all over. 60 sft
- 3 Table Refabrication - Laminate top and  
repairs. 4 nos
- 4 Shifting of Partitlon
- 5 New Partition 35 sft
- 6 Mislenious work such as Soft board, Cable  
Manager, Curtain rod, hook etc.
- 7 Removing old work including plastering to  
hook, shifting debries, etc

**TOTAL AMOUNT**